The drawings referred to above can be had from the undersigned on application.

The thimbles should be made of the best quality seasoned wood suitable for the purpose. They should be thoroughly impregnated with paraffin. Samples of the thimbles offered should be sent with the quotation.

The supply should be made in monthly instalments of 3,000 to 4,000 thimbles in the case of item 1 and 1,000 thimbles in the case of items 2 and 3.

The prices to be quoted should be for delivery, c.i.f., Madras and f.o.r., Bangalore or free delivery at the Government Porcelain Factory, Bangalore.

This enquiry will close on the 7th of October 1940.

Yours faithfully,
MIR SAFDAR HUSSAIN,
Secretary,
Stores Purchase Committee.

No. S. P. C. 4626-27, *dated* 19*th August* 1940.

NOTICE.

Enquiry No. 4145.

Sealed tenders will be received by the Secretary, Stores Purchase Committee, for the supply of Tools and Plant required for the Eectrical Department, up to 30th September 1940.

Intending tenderers may, on application to the Secretary, Stores Purchase Committee, obtain the requisite tender forms on which tenders should be submitted. Applications should be accompanied by a cash remittance of Rs. 3 which is the price fixed for a set of forms and which is not refundable.

Cheques and postage stamps will not be accepted towards the cost of forms nor will the forms be sent by V. P. P.

By Order,
MIR SAFDAR HUSSAIN,
Secretary,
Stores Purchase Committee.

No. S. P. C. 4654, *dated* 20*th August* 1940.

NOTICE.

Enquiry No. 4175.

PAINTS REQUIRED FOR THE MYSORE STATE RAILWAY DEPARTMENT DURING THE YEAR 1940-41.

The closing date of the above enquiry is extended up to 6th September 1940.

MIR SAFDAR HUSSAIN,
Secretary,
Stores Purchase Committee.

ENGINEERING DEPARTMENT.

BUILDINGS DIVISION, BANGALORE.

Notification dated 20*th August* 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 2 P.M. on 2nd September 1940 for constructing a building for preparing glandular products in the Industrial and Testing Laboratory, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 250 Two hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a building for preparing glandular products in the Industrial and Testing Laboratory, Bangalore, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any tender quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a building for preparing Glandular Products in Industrial and Testing Laboratory, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement in 6″ layers including watering, tamping, etc., complete	C.yds.		95	
2	Granite jelly concrete in lime mortar laid in layers, of 6″ with necessary consolidation ..	C.ft.		515	
3	Size stone in lime mortar with bond stones at every 6′ apart in courses not less than 6″ to 7″ height for foundation and one line quoin dressed 2″ to 3″ wide for basement ..	,,		1,751	
4	R. C. C. 6″ slab for basement 1 : 2 : 4 proportion with necessary reinforcement, etc., complete.	S.ft.		206	
5	Burnt brick in lime mortar for superstructure including proper bond stones wherever necessary	C.ft.		1,503	
6	Size stone in lime mortar pillars of 2′×2′×13′ with necessary bonds and plastering if necessary, etc., complete	R.ft.		78	
7	Burnt stone slabs 6″ thick, one line dressed and fixed in lime mortar	S.ft.		48	
8	Teakwood door 4″×5″ frame, 1½″ thick panelled shutters, hooks, hinges, bolts, including iron fittings, etc., complete	,,		48	
9	Teakwood windows 4″×5″ frame glazed shutters in four halves and ¾″ iron-bars placed at 4″ apart including parliamentary hinges and iron fittings, etc., complete	,,		270	
10	Removing and refixing old windows with necessary repairs if any with new screws, etc. ..	,,		115½	
11	Tata's tested rolled steel girders including hoisting and fixing in place with bolts, etc., and with a coat of anti-corrosive paint and bed plates and cement concrete	Cwt.		84	
12	R. C. C. roofing for a span of 10 feet to take a load of 1½ Cwt. per sq. ft. with 3″ surki concrete over two courses of flat tiles and plastering at top complete	Sqrs.		14·19	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
13	R. C. C. chejja 3′ wide and 3′ thick, bearing to full thickness wall with plastering all sides, including extra reinforcement at corners and also reinforcement for slab over window ..	S.ft.		336	
14	Plain cornice as per design to be given alround ..	R.ft.		106	
15	Burnt brick in lime mortar parapet wall of 1½′ high and 9″ thick including plastering and finishing the top complete	,,		106	
16	Dismantling old wall for constructing pillars with supports and clearing debris	C.ft.		229	
17	Closing the window opening with burnt brick in lime mortar	,,		162	
18	Removing the alternate courses of old wall to give proper bond to old and new structure ..	R.ft.		30	
19	Cement pointing for basement 1″ deep ..	Sqrs.		2·12	
20	Lime mortar plastering, two coats	,,		36·31	
21	Government Lac Factory green painting, two coats	,,		8·66	
22	Zinc sheet rectangular rain water pipes 3″×4″ including fixing in position	R.ft.		102	
23	White and colour washing, two coats	Sqrs.		36·51	
24	Flooring with 1½″ cement concrete over 3″ of lime concrete finished with red ochre at top including with cut lines, etc., complete ..	,,		12·00	

Notification dated 20th August 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 2 P.M. of 13th September 1940, for constructing a building for manufacturing crockery articles in the Government Porcelain Factory, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury chellan for the deposit of Rs. 355, as earnest money, and be superscribed "Tender for constructing a building for manufacturing crockery articles in the Government Porcelain Factory, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any tender quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a building for manufacturing crockery articles in Government Porcelain Factory, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement with extra earth if necessary with consolidation	C.yd.		248	
2	Granite jelly concrete in lime mortar laid in layers of 6″ and proper tamping ..	C.ft.		1,136	
3	Size stone in lime mortar with bond stones at 6′ apart for foundations basement quoin dressed for basement 2″ to 2½″ wide ..	,,		5,053	
4	Providing 6″ burnt stone slabs 2 line dressed on exposed faces rough dressed on other sides fixed in lime mortar for basement ..	S.ft.		564	
5	Burnt brick in lime mortar for superstructure with necessary bond stones	C.ft.		4,150	
6	Providing and fixing Teakwood doors with 1¼″ panelled shutters and iron fittings and 4″×5″ frame	S.ft.		201	
7	Teakwood windows of standard frames, iron fittings and glazed shutters both fixed and openable as per details to be given during execution	,,		520	
8	Burnt stone slabs 6″ roughly dressed and fixed for lintels and cills	,,		341	
9	Providing and hoisting fixing M. S. trusses for a clear span of 25′ including anti-corrosive paint, Anchor bolts, bed plates, drilling holes in slabs, cement concrete, etc., complete ..	Cwt.		30	
10	Do angle iron purlins 2″×2″×¼″ and fixing with bolts and nuts, painting, including hoisting, etc., complete ..	,,		14	
11	Roofing with corrugated red trafford sheets including fixing with bolts and nuts, washers and also hoisting, etc., complete	Sqr.		31·50	
12	Ridging with red trafford sheets including fixing	R.ft.		87½	
13	Lime mortar plastering 2 coats	Sqr.		59·63	
14	White and colour washing 2 coats	,,		59·63	
15	Painting with Lac Factory green paint 2 coats	,,		14·42	
16	Casting R. C. C. slabs of the required thickness	C.ft.		72	
17	Cement pointing to basement 1″ deep ..	Sqr.		5·70	
18	Providing and fixing burnt stone slabs 6″ thick fixed in lime mortar exposed faces dressed	S.ft.		54	
19	Flooring with 1½″ cement concrete laid over 4″ lime concrete with cement plastering ½″ and smooth finish, lines cut, etc., complete ..	Sqr.		20·26	
20	Mortar band at ends of roof	R.ft.		64	
21	Providing and fixing T. W. eave board ¾″×9″ ..	,,		456	
22	Do T. W. pendents ..	No.		4	

M. K. RAJAM IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF INDUSTRIES AND COMMERCE.

OFFICE OF THE SUPERINTENDENT, CENTRAL INDUSTRIAL WORKSHOP, BANGALORE.

Notice dated 22nd July 1940.

Sealed tenders will be received at the Office of the Superintendent, Government Central Industrial Workshop, Bangalore, up to 3 o'clock on Monday the 2nd September 1940, from